

DPPS

COST ESTIMATE

A cost estimate to remove the identified ACM is provided in the following table, T-1:

**TABLE T-1
ESTIMATED COST OF ABATEMENT**

RECOMMENDED ACTION	UNITS	UNIT COST	ESTIMATED COST*
Removal of transite panel fume hoods	175 s.f.	\$5.00/s.f.	\$875.00
Removal of brown window and door frame caulk compound	1,550 l.f.	\$4.00/l.f.	\$6,200.00
Removal of gray exterior building caulk compound	90 l.f.	\$4.00/l.f.	\$360.00
Removal of brown window glaze compound	165 l.f.	\$4.00/l.f.	\$660.00
Removal of roofing materials	10,000 s.f.	\$6.00/l.f.	\$60,000.00
Removal of fire doors and frames	9 units	\$225.00/unit	\$2,025.00

GRAND ESTIMATED TOTAL \$70,120.00

* The cost estimates are based on current industry prices. Industry prices may change at any time. It is assumed that the work is performed by licensed, competent organizations. Estimates include all costs of abatement projects except replacement. Estimated cost is based on project size, difficulty, access, and all work being done at one time, etc. Some savings may be possible by combining projects.